

# HCC 2026

## 67% Status Update

### Team

Nathaniel Holguin


Karsten Jones

Anthony Nuzzo


Dawson Stevens

# PROJECT OVERVIEW

- **Competition:** DOE Hydropower Collegiate Competition
- **Scope:** Research driven feasibility, modeling, and prototype validation
- **Design Goal:** Develop competition ready hydropower system concepts




# DESIGN EVOLUTION & FINAL CONCEPT



## Updates:

- Adjusting scales for rapid prototyping and testing
- Using a 0.014 scale for Prony Brake
- Updated some tolerances, to make less snug for rpm testing
- Increased size of the magnet generator housing


# Flow Duration Curve (Daily Mean)



- Q10- 631 m<sup>3</sup>/s
- Q50- 220 m<sup>3</sup>/s
- Q90- 90 m<sup>3</sup>/s
- Q<sub>min</sub> - 47 m<sup>3</sup>/s

Daily discharge exceeds 90 m<sup>3</sup>/s 90% of the time, indicating strong base flow reliability for our constraints.

# Coon Rapids PDC Estimate




- 7 unused turbine housings
- Using already existing Powerhouse
- This screening simulates taking advantage of about 15% of flows
  - 10 m<sup>3</sup>/s flow per turbine standard(Voith).
  - option for more turbines, this is a general screening using a max of 5 generation units.
  - Site not governed by head(5.8m), generous flows

# Coon Rapids PDC Estimate



Current options based on assumptions, more info to update next week.

- Low power based on # of units (10m<sup>3</sup>/s per unit)
- modeled over 15% usage
- Best case- 4 units, .75CF, better LCOE compared to 5 units, safer cushion compared to 3 units.
- Needs some sort of copower/option to validate at this stage.




3 modules		Qcap=30.0 m <sup>3</sup> /s		Rated=1.30 MW		Avg=1.09 MW		CF=0.84
4 modules		Qcap=40.0 m <sup>3</sup> /s		Rated=1.74 MW		Avg=1.30 MW		CF=0.75
5 modules		Qcap=50.0 m <sup>3</sup> /s		Rated=2.17 MW		Avg=1.45 MW		CF=0.67

# Coon Rapids LMP Proxy Estimate



- Summer median pricing exceeds winter median
- Winter Scarcity brings high value hours
- Summer peak demand brings consistent pricing


# Coon Rapids LMP Proxy Estimate



Season	Mean (\$/MWh)	Median (\$/MWh)	P95 (\$/MWh)
"Winter (Jan-Feb)"	"\$58.2"	"\$34.9"	"\$163.7"
"Summer (Jul-Aug)"	"\$60.5"	"\$42.2"	"\$134.8"

- Summer median pricing exceeds winter median, indicating stronger typical peak demand value
- Winter exhibits higher upper-tail volatility(P95) due to scarcity events
- Hydro production aligns with both seasonal peak demand and high-value scarcity hours.

# Prony Brake Design Analysis



- Wood Frame
- 3D printed turbine
- Stainless Steel Shaft
- Aluminum Machined Drum
- Sensors
- Dyneema Cord
- Dead Weight


# ENVIRONMENTAL ANALYSIS

Used ORNL's Environmental Decision Toolkit

- Active Fishery - Fish screens can prevent entry into turbine system
- Invasive Carp\* - Need to prevent upstream spread
- Water Oxygenation - Impact should be minimal or nonexistent



\*Carp may have already passed through the dam



# Non-Dimensional Analysis

- Based on the Hydropower Equation to compare results
- Equations to scale down our project so that we accurately test our prototype
- Modified to be able to work with a garden hose or similar flow

$$D_p = D_m \sqrt{\frac{Q_p}{Q_m} \sqrt{\frac{H_m}{H_p}}} \quad (4)$$

Plugging in the variables to solve for  $D_p$ .

$$D_p = 1.3 \sqrt{\frac{0.0024}{13} \sqrt{\frac{8}{1}}} = 0.0297\text{m} \cong 3\text{cm}$$

The result isn't limited by the 3D Printing area which is 400mm x 400mm x 400mm. Using equation (1) we can predict the power output to be 0.87 MW or 870,000 W. Setting  $P_m = 870,000\text{W}$  in equation (3) results in  $P_p = 20.5\text{W}$ .

$$P_p = 870,000 \left(\frac{.03}{1.3}\right)^2 \left(\frac{1}{8}\right)^{3/2} = 20.5\text{W}$$

To verify the calculations, we can check the new flow rate with equation (1), and see if the results are consistent.

$$P = 1000 \text{ kg/m}^3 \times 9.81 \text{ m/s}^2 \times 1 \text{ m} \times 0.0024 \text{ m}^3/\text{s} \times 0.85 = 20\text{W}$$

The difference is 0.5W or a 2.5% margin of error. This is less than 5%, this is an acceptable result.

Corbin Davis- Non-dimensional Analysis

# SCHEDULE

## ME486C - HCC26 Gantt

Task name	Start date	End date	Assigned	Status	23-Feb	24-Feb	25-Feb	26-Feb	27-Feb	28-Feb	1-Mar	2-Mar	3-Mar	4-Mar	5-Mar	6-Mar	7-Mar	8-Mar	9-Mar	10-Mar	11-Mar	12-Mar	13-Mar	14-Mar	15-Mar	16-Mar	17-Mar	18-Mar	19-Mar	20-Mar	21-Mar	22-Mar	23-Mar	24-Mar	25-Mar	26-Mar	27-Mar	28-Mar	29-Mar	30-Mar	31-Mar							
<b>February Competition Submissions</b>	12-Jan	23-Feb	ME Team	Done	█																																											
Siting Challenge	13-Jan	23-Feb	ME Team	Done	█																																											
Design Challenge	14-Jan	23-Feb	ME Team	Done	█																																											
Community Connections	15-Jan	23-Feb	ME Team	Done	█																																											
Build and Test	16-Jan	23-Feb	ME Team	Done	█																																											
<b>67% Build</b>	4-Feb	24-Feb	ME Team	Done	█	█																																										
Validating Manufactured Components	4-Feb	24-Feb	ME Team	Done	█	█																																										
Validating Subsystem Integration	4-Feb	24-Feb	ME Team	Done	█	█																																										
Cost Models Refined using as-built	4-Feb	24-Feb	ME Team	Done	█	█																																										
Environmental and Operational Check	4-Feb	24-Feb	ME Team	In process	█	█																																										
Prony Brake Build and Test	4-Feb	5-Mar	ME Team	In process			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█			
New Site Analyses/Feasibility	20-Feb	2-Mar	ME Team	In process			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█		
Interviews of Industry Problems	20-Feb	10-Mar	ME Team	In process			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█		
Design Track	20-Feb	15-Mar	ME Team	In process			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	
<b>Finalized Testing Plan</b>	25-Feb	20-Mar	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	
100% build	25-Feb	26-Mar	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	
<b>Final Poster and Final PPT</b>	25-Feb	10-Apr	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
<b>Final siting and technical design repo</b>	25-Feb	12-Apr	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
<b>Final Product Demo Multiplier</b>	1-Mar	16-Apr	ME Team	Open																																												
<b>Final Report (Capstone)</b>	25-Feb	17-Apr	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
<b>Metrics Report</b>	25-Feb	19-Apr	ME Team	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
<b>Final Website Check</b>	25-Feb	21-Apr	Nathaniel	Open			█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
<b>Design and Siting Poster</b>	1-Mar	27-Apr	ME Team	Open																																												

# BUDGET STATUS

No.	Date	Department	Purposes	Demand detail				Procurement details			Handler	State
				Product	Model	Unit	Quantity	Date	Price	Amount		
1	2026/02/25	Mechanical	Prony Brake	PGN Bearings	12x28x8 mm	***	2	2026/03/10	\$7.00	14.00	PNGBearings	In Process
2	2026/02/25	Mechanical	Prony Brake	Neiko 20713A Digital Laser Tachometer	Neiko 20713A	***	1	2026/03/10	\$30.00	30.00	Autozone	In Process
3	2026/02/25	Mechanical	Prony Brake	Digital Push Pull Force Gauge	AMF-50N	***	1	2026/03/10	\$50.00	50.00	Friday Parts	In Process
4	2026/02/25	Mechanical	Prony Brake	Dyneema cord	UHMWPE Braided Cord	***	1	2026/03/10	\$18.00	18.00	Amazon	In Process
5	2026/02/25	Mechanical	Prony Brake	Stainless Steel shaft	12mm, 303 stainless steel, corrosion resistant, 1ft/300mm length	***	1	2026/03/10	\$32.00	32.00	McMaster	In Process

What are our expenses to date?		
Description	Expense amount	
3d Printer	Artizan snapmaker 3D 3in1 printer	\$2,882.94
Machined metal shaft	7 inch metal shaft	\$10.00
Team Shirts	Team shirts x8	\$125.00
PGN Bearings	12x28x8 mm bearings x2	\$14.00
Neiko 20713A Digital Laser Tachometer	Neiko 20713A	\$40.00
Digital Push Pull Force Gauge	AMF-50N	\$50.00
Dyneema cord	UHMWPE Braided Cord	\$18.00
Stainless Steel shaft	12mm, 303 stainless steel, corrosion resistant, 1ft/300mm length	\$32.00
<b>Total Expenses</b>		<b>\$3,171.94</b>
<b>True remaining balance</b>		<b>\$14,828.06</b>

State	Amount	Ratio
In Process	194.00	100%
Complete	-	0%

# Moving Forward

## Design Challenge

- Model Capex and nodal grid data to track economic feasibility
- Finalize copower opportunities (Solar, Recreation)
- Finalize turbine intake setup/placement following meeting with Site advisors
- Construct build drawings of proposed concepts

## Community Connections

- Planning more outreach events (schools/energy club involvement)
- Meet with Coon Rapids Dam

## Build & Test

- Build and test aspects generator/prony brake
- Finalize purchasing plan & manufacturing plan
- Planning more outreach events (schools/energy club involvement)

**THANK YOU!**